## **Declaration of Performance**




**ACP(Concrete) Ltd,** Lakes Road, Workington

Lakes Road, Workington
Cumbria, CA15 3YP

13

Factory production control 0086-CPR-600822

## **EN 1168**



## **Precast concrete products**

## Wideslabs for flooring

Concrete	<b></b>
Compressive strength fck	50N/mm <sup>2</sup>
Prestressing Steel	
Ultimate tensile strength fpk	1770N/mm2
Tensile 0.1% proof stress f <sub>p0,1k</sub>	1500N/mm <sup>2</sup>
Dimensions in mm	75 x 1147
Length	See design drawings for
(up to a max of $5m \pm 25mm$ )	individual lengths
<b>Strands Y1770-9.3</b>	10no max.
Initial stress	1239N/mm <sup>2</sup>
End protrusion of strands l	0mm
For detailing and durability	See web site
Technical information	See web site

The performance of this Product complies with the Design and Harmonised Codes applicable to that product. The relevant code, performance criteria and factory identifier are shown. The design drawings and calculation detail the design codes and physical dimensions of the product.

The initial factory inspection has been completed by BSI (Notifying Body 0086) and the continuous surveillance, assessment and evaluation of the Factory Production control is declared as compliant for all products of this type.

W Mercer Managing Director 11/03/16